

## Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

## Krishi Vigyan Kendra, Wardha



At Post - Selsura, Tq. Dist.- Wardha

Out. No. KVK/Sel/939/2023

Dated 30.06.2023

## **QUOTATION NOTICE**

Subject - Providing Water Supply Pipeline at KVK Selsura, Tah. Deoli, Dist. Wardha

Sealed quotations are invited in the name of undersigned from Authorised Agencies (For the Name of work - Providing Water Supply Pipeline at KVK Selsura, Tah.Deoli, Dist.Wardha.) so as to reach in this office on or before <u>07/07/2023</u> upto 3.00 pm for the following item.

The quotation will be opended on the same date. The right to reject any or all quotation or to calling fresh quotations reserved by the undersigned without assigning any reason there on.

The rates should be quoted including all taxes (with GST) charges delivery site of work. Quotation received after the prescribed date will not be accepted. The item of work enquiry No. & due date quoted clearly and written on the top of the envelope. The delivery period be mentioned in the quotation rates should be written in figures and words clearly.

## List of Item

Sr. No.	Item of work	Qty.	Unit	Rate Quoted	Amount
1	2		3	4	5
1	Providing ISI mark G.I. pipe of following class and 150 mm dia. (19.70 kg/mt) excluding GST levied by GOI & GOM in all respect, inspection charges, transportation to stores, etc. complete as per IS-1239/2004.  Note: One coupler shall be provided with each full length of pipe cost of which is included in rates below.	85.00	Rmt		
2	Providing and laying in trenches 50 mm dia. medium grade having embossed as ISI Mark galvanised iron pipes of 5.17 Kilogram/meter necessary fitting remaking good the demolished portion with filling trenches and with primer of anti-corrosive oil paint, 2 coats Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	Rmt		
3	Providing and fixing screw down for 50 mm dia. wheeled stop tap of brass including necessary sockets/ union nut complete.	8.00	Rmt		



4	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)		Cum	
5	Providing and fixing 160mm Saddle to 150mm dia Pipe for taking 50mm dia connection at upper level including necessary labour claches and excavation etc. complete as directed.	8.00	Nos	
6	Providing SDP MTA including labour charges for fixing it in position to attach sprinkler pipe etc. complete as directed.	8.00	Nos	
7	Engazing JCB for excavation / dismentalling the old pipeline etc. complete as directed.	5.00	Hours	
	Total Amount Rs.			

Senior Scientist and Head, KVK Selsura, Dist.Wardha